



Building Community®

Procurement Department Bid Office
225 N. Pearl St.
Jacksonville, Florida 32202

August 26, 2024

ADDENDUM NUMBER: Three (3)

TITLE: Kennedy Substation Anode Bed Replacement

JEA SOLICITATION NUMBER: 1411830848

RESPONSE DUE DATE: August 27, 2024

TIME OF RECEIPT: 12:00 PM

TIME OF OPENING: 2:00 PM

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

1. **QUESTION:** Are we removing the existing rectifier and mounting the new rectifier in the same place?

ANSWER: Yes.

2. **QUESTION:** How far will the groundbed be from the rectifier?

ANSWER: Roughly 180-200ft depending on the final location of the ground bed. As per the spec, all trenching within the substation will need to be dug by hand.

3. **QUESTION:** How deep do you want the trench for the new conduits & cables?

ANSWER: Minimum 18in.

4. **QUESTION:** What is the address of where this installation will be?

ANSWER: 4215 Talleyrand Ave Jacksonville FL 32206